

BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

NAME OF THE WORK:- Improvements to Roads of 1st to 11th Cross Left side of Jakkur Layout in Ward No 07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Issued to	
				Technical Manager , KRIDL	
				In Figures	In Words
1	633.60	Removing and resetting of footpath slab (P.No.142, I.No.37.56 of PW,P&IWTD S.R 2016-17)	sqm	132.50	Rupees One Hundred Thirty Two and Fifty Paise Only
2	217.44	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.133, I.No.19.1 of PW, P&IWTD SR 2016-17)	cum	186.92	Rupees One Hundred Eighty Six and Ninety Two Paise Only
3	63.72	KSRRB 5.3-1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.(P-235. Item No. 5.6)	cum	4438.22	Rupees Four Thousand Four Hundred Thirty Eight and Twenty Two Paise Only
4	141.60	KSRRB 5.3-1:Providing ruled pointing of course stone masonry with cement mortar 1:3 20 mm deep, after raking joints to depth of 20 mm nicley lining, including cost of materials, labour, curing etc., complete as per specifications and directions of the engineer-in-charge. (P-112, Item No. 15.8)	sqm	34.98	Rupees Thirty Four and Ninety Eight Paise Only
5	18.60	KSRRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complete as per specifications. (Page No. 12. Item No. 4.6)	cum	5767.46	Rupees Five Thousand Seven Hundred Sixty Seven and Forty Six Paise Only
6	305.40	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	sqm	2100.00	Rupees Two Thousand One Hundred Only
7	21.60	Providing and fixing RCC Precast cover slab of 200mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	sqm	5111.00	Rupees Five Thousand One Hundred Eleven Only
8	469.00	Removing and resetting of kerb stones(P.No.142, I.No.37.57 of PW,P&IWTD S.R 2016-17)	m	65.72	Rupees Sixty Five and Seventy Two Paise Only
9	447.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete(P.No.25, I.No.5.30 of PW,P&IWTD S.R 2016-17)	No	331.78	Rupees Three Hundred Thirty One and Seventy Eight Paise Only
10	70.51	KSRRB M300-14. Excavation for roadwork in soil with hydraulic excavator of 0.90 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to embankment location and complete as per specifications. MORTH Specification No.301 (P.No.142, I.No.19.14 of PW,P&IWTD S.R 2016-17)	cum	148.76	Rupees One Hundred Forty Eight and Seventy Six Paise Only

EXECUTIVE ENGINEER-4
Byatarayanapura Division
BENGALURU-560 010

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
11	70.51	KSRRB M 400-17, Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage ' of mixed Material by tipper to site, laying in uniform layers with paver in sub- base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 (P.No.157, I.No.20.18 of PW,P&IWTD SR 2016-17)	cum	1768.08	Rupees One Thousand Seven Hundred Sixty Eight and Eight Paise Only
12	306.56	KSRRB M 500-6, Providing and applying primer coat with SS bitumen emulsion on prepared surface of granular Base such as WBM WMM including clearing of road surface and spraying primer at the rate of 0.60 kglsgm using mechanical means complete as per specifications. As per MORTH specification clause No. 502 (P.No.160, I.No.21.6 of PW,P&IWTD SR 2016-17)	sqm	27.56	Rupees Twenty Seven and Fifty Six Paise Only
13	9048.00	KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH Spec, Chapter 5 (P.No.160, I.No.21.2 of PW,P&IWTD SR 2016-17)	sqm	3.18	Rupees Three and Eighteen Paise Only
14	9048.00	KSRRB M500-7 : Providing and applying tack coat using 80/100 grade bitumen (VG10) on prepared black topped surfaces at 2.5 Kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.MORTH / Chapter 5 (P.No.160 I.No.21.7 of PW,P&IWTD SR of 2016-17)	sqm	11.66	Rupees Eleven and Sixty Six Paise Only
15	360.66	KSRRB M500-19. Providing and laying bituminous concrete 40 mm compacted thickness with VG30 Bitumen grade using 40-60 HMP using crushed aggregates of grading II, premixed with bituminous binder at 6% of mix and filler, transporting the hot mix to work site, laying with a mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification clause No. 500.9 complete in all respects as per specifications. MORTH Specification No. 509 (P.No.164 of I.No.21.22.6 in PW,P&IWTD S.R 2016-17)	cum	7083.98	Rupees Seven Thousand Eighty Three and Ninety Eight Paise Only
16	320.80	KSRRB M800-13. Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803.(P.No.197, I.No.24.15 of PW,P&IWTD SR 2016-17)	sqm	542.72	Rupees Five Hundred Forty Two and Seventy Two Paise Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

[Signature]
Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'.

[Signature]
EXECUTIVE ENGINEER-4
CONTRACTOR
KRIDL, BBMP DIVISION
BENGALURU-560 010